



Extraction Area	layer	Area (ha)
1	Extraction No OB	1.6
4	Extraction No OB	0.8
2	Extraction With OB	0.6
3	Extraction With OB	0.2
5	Extraction With OB	0.6

Soils (m3)					
AREA	CUT_VOLUME	CUT_AREA (ha)	Avg Thickness	Max Thickness	Min Thickness
1	4,684	1.56	0.3	0.3	0.3
4	2,257	0.75	0.3	0.3	0.3
2	1,789	0.60	0.3	0.3	0.3
3	571	0.19	0.3	0.3	0.3
5	1,764	0.59	0.3	0.3	0.3
Totals	11,065	3.69			

Overburden (m3)					
AREA	CUT_VOLUME	CUT_AREA (ha)	Avg Thickness	Max Thickness	Min Thickness
1	-	0.00	-	-	-
4	-	0.00	0.0	0.0	0.0
2	6,250	0.54	1.0	3.3	0.0
3	5,020	0.19	2.6	5.1	1.2
5	6,158	0.53	1.0	3.6	0.0
Totals	17,427	1.26			

Gravel (Pit Run) (m3)					
AREA	CUT_VOLUME	CUT_AREA (ha)	Avg Thickness	Max Thickness	Min Thickness
1	69,560	1.56	4.5	5.9	2.4
4	21,383	0.75	2.8	4.5	1.1
2	16,978	0.59	2.9	5.0	0.0
3	5,458	0.19	2.9	4.4	1.2
5	18,169	0.58	3.1	4.9	0.1
Totals	131,548	3.68			



LEGEND

- SML 090016 Survey Plan Boundary
- 100m Buffer
- 60m Buffer
- Extraction Areas Combined**
- Extraction No OB
- Extraction With OB